

ITEM 619.04 (EA)			
TYPE III CONSTRUCTION BARRICADES			
STATION	SIDE	WZTC COMMENTS	QTY. (EA)
US RT 9W - MP 123.69 (BIN 1053550)			
		STAGE A	12
		STAGE B	4
			20
TOTAL:			20

Added for unanticipated field conditions:			
SAY:			20

[STANDARD SHEETS FOR 619](#)

PREPARED BY: G. KEHN

CHECKED BY: C. CORNWELL

ITEM 619.0803 (LF)			
COVER EXISTING PAVEMENT MARKING STRIPES (REMOVABLE TAPE)			
FROM STATION	TO STATION	COMMENTS	LENGTH (FT)
US RT 9W - MP 123.69 (BIN 1053550)			
		WHITE EDGE	4,865
		YELLOW PARTIAL BARRIER	1,300
		YELLOW FULL BARRIER	5,640
		YELLOW HATCH	2,044
			13,850
GLENMONT RD - MP 139.54 (BIN 1022440)			
		WHITE EDGE	1,480
		YELLOW FULL BARRIER	1,480
			2,960
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		WHITE EDGE	1,530
		YELLOW FULL BARRIER	1,880
			3,410
TOTAL:			20,220

Added for unanticipated field conditions:	
SAY:	20,220

PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

619.0804 (EA)		
COVER EXISTING PAVEMENT MARKING LETTERS OR SYMBOLS (REMOVABLE TAPE)		
STATION	COMMENTS	QTY. (EA)
US RT 9W - MP 123.69 (BIN 1053550)		
	WHITE TURNING ARROWS	10
TOTAL:		10

Added for unanticipated field conditions:	
SAY:	
	10

PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.100104 (LF) INTERIM PAVEMENT MARKINGS, STRIPES (REMOVABLE WET REFLECTIVE TAPE)						
FROM STATION	TO STATION	TYPE	COMMENTS	LENGTH (FT)	WIDTH (IN)	PAID LENGTH (LF)
US RT 9W - MP 123.69 (BIN 1053550)						
STAGE A			WHITE EDGE	154	4	154
			YELLOW EDGE	154	4	154
			YWL FULL BARRIER	830	4	1,660
			YELLOW HATCH		24	2,739
STAGE B			WHITE EDGE	4,720	4	4,720
			YELLOW EDGE	154	4	154
			YWL FULL BARRIER	154	4	307
			YELLOW HATCH		24	2,803
						12,700
						0
GLENMONT RD - MP 139.54 (BIN 1022440)						
STAGE A			WHITE EDGE	730	4	730
			STOP BARS	35	12	105
STAGE B			WHITE EDGE	730	4	730
			STOP BARS	35	12	105
						1,670
						0
MARIAVILLE RD - MP 159.23 (BIN 1038760)						
STAGE A			WHITE EDGE	1,680	4	1,680
			STOP BARS	46	12	138
STAGE B			WHITE EDGE	1,340	4	1,340
			STOP BARS	46	12	138
						3,300
						0
						0
TOTAL:						17,670

Added for unanticipated field conditions:	
SAY:	17,670

PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

619.110513 (EA)		
PORTABLE VARIABLE MESSAGE SIGN		
STATION	COMMENTS	QTY. (EA)
	US RT 9W - MP 123.69 (BIN 1053550)	2
	US RT 9W - MP 123.69 (BIN 1053550) - I-87 NYS THRUWAY	2
		4
	GLENMONT RD - MP 139.54 (BIN 1022440)	2
	GLENMONT RD - MP 139.54 (BIN 1022440) - I-87 NYS THRUWAY	2
		4
	MARIAVILLE RD - MP 159.23 (BIN 1038760)	2
	MARIAVILLE RD - MP 159.23 (BIN 1038760) - I-90 NYS THRUWAY	2
		4
TOTAL:		12

PREPARED BY: G. KEHN

CHECKED BY: C. CORNWELL

ITEM 619.1302XX (ELOC)			
TEMPORARY TRAFFIC SIGNAL [XX = SERIALIZED]			
LOCATION	COMMENTS	PHASE	EACH LOCATION
GLENMONT RD - MP 139.54 (BIN 1022440)		A	1
		B	1
			2
MARIAVILLE RD - MP 159.23 (BIN 1038760)		A	1
		B	1
			2
TOTAL:			4

Added for unanticipated field conditions:	
SAY:	4

PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.17060025 (LF)			
LINEAR DELINEATION SYSTEM			
FROM STATION	TO STATION	COMMENTS	LENGTH (FT)
US RT 9W - MP 123.69 (BIN 1053550)			
		MAINLINE SHOULDERS	72.00
		MAINLINE MEDIAN	64.00
			140.00
GLENMONT RD - MP 139.54 (BIN 1022440)			
		MAINLINE SHOULDERS	72.00
		MAINLINE MEDIAN	72.00
			150.00
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		MAINLINE SHOULDERS	72.00
		MAINLINE MEDIAN	72.00
			150.00
TOTAL:			440.00
Added for unanticipated field conditions:			
SAY:			440

[STANDARD SHEETS FOR 619](#)

PREPARED BY: G. KEHN

CHECKED BY: C. CORNWELL

ITEM 619.1711 (LF)			
TEMPORARY POSITIVE BARRIER, [CAT 1]			
FROM STATION	TO STATION	COMMENTS	LENGTH (FT)
US RT 9W - MP 123.69 (BIN 1053550)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	
			0.00
GLENMONT RD - MP 139.54 (BIN 1022440)			
		STAGE A	590.00
		STAGE B	630.00
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	
			1,220.00
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	
			0.00
TOTAL:			1,220.00

Added for unanticipated field conditions:	
SAY:	1,220

STANDARD SHEETS FOR 619
 PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.1713 (LF)			
TEMPORARY POSITIVE BARRIER, [CAT 3]			
FROM STATION	TO STATION	COMMENTS	LENGTH (FT)
US RT 9W - MP 123.69 (BIN 1053550)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	
			0.00
GLENMONT RD - MP 139.54 (BIN 1022440)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	
			0.00
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		STAGE A	690.00
		STAGE B	620.00
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	
			1,310.00
TOTAL:			1,310.00

Added for unanticipated field conditions:	
SAY:	1,310

STANDARD SHEETS FOR 619
 PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.1714 (LF)			
TEMPORARY POSITIVE BARRIER, [CAT 4]			
FROM STATION	TO STATION	COMMENTS	LENGTH (FT)
US RT 9W - MP 123.69 (BIN 1053550)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	740.00
			740.00
GLENMONT RD - MP 139.54 (BIN 1022440)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	780.00
			780.00
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	
		MAINLINE MEDIAN	360.00
			360.00
TOTAL:			1,880.00

Added for unanticipated field conditions:	
SAY:	1,880

[STANDARD SHEETS FOR 619](#)
 PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.1715 (LF)			
TEMPORARY POSITIVE BARRIER, [CAT 5]			
FROM STATION	TO STATION	COMMENTS	LENGTH (FT)
US RT 9W - MP 123.69 (BIN 1053550)			
		STAGE A	910.00
		STAGE B	990.00
		MAINLINE SHOULDERS	1,060.00
		MAINLINE MEDIAN	
			2,960.00
GLENMONT RD - MP 139.54 (BIN 1022440)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	1,080.00
		MAINLINE MEDIAN	
			1,080.00
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		STAGE A	
		STAGE B	
		MAINLINE SHOULDERS	980.00
		MAINLINE MEDIAN	360.00
			1,340.00
TOTAL:			5,380.00

Added for unanticipated field conditions:	
SAY:	5,380

STANDARD SHEETS FOR 619
 PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.1719 (LF)			
Warning Lights on Temporary Positive Barriers			
FROM STATION	TO STATION	COMMENTS	EACH (EA)
US RT 9W - MP 123.69 (BIN 1053550)			
		STAGE A	22.75
		STAGE B	24.75
			50.00
GLENMONT RD - MP 139.54 (BIN 1022440)			
		STAGE A	14.25
		STAGE B	16.00
			40.00
MARIAVILLE RD - MP 159.23 (BIN 1038760)			
		STAGE A	16.75
		STAGE B	15.75
			40.00
TOTAL:			~~90.00~~ 130

Added for unanticipated field conditions:	
SAY:	~~90~~ 130

[STANDARD SHEETS FOR 619](#)

PREPARED BY: G. KEHN

CHECKED BY: C. CORNWELL

ITEM 619.1802 (EA)				
TEMPORARY IMPACT ATTENUATOR - REDIRECTIVE (TEST LEVEL 2)				
STATION	OFFSET	SIDE	COMMENTS	QTY. (EA)
RT 9W - MP 123.69 (BIN 1053550)				
				0
GLENMONT RD - MP 139.54 (BIN 1022440)				
				0
MARIAVILLE RD - MP 159.23 (BIN 1038760)				
			STAGE A	1
			STAGE B	1
				2
TOTAL:				2

Added for unanticipated field conditions:	
SAY:	2

PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL

ITEM 619.1803 (EA)				
TEMPORARY IMPACT ATTENUATOR - REDIRECTIVE (TEST LEVEL 3)				
STATION	OFFSET	SIDE	COMMENTS	QTY. (EA)
RT 9W - MP 123.69 (BIN 1053550)				
			STAGE A	1
				1
GLENMONT RD - MP 139.54 (BIN 1022440)				
				0
MARIAVILLE RD - MP 159.23 (BIN 1038760)				
			MAINLINE - SHOULDERS	1
			MAINLINE - MEDIAN	2
				3
TOTAL:				4

Added for unanticipated field conditions:	
SAY:	4

PREPARED BY: G. KEHN
 CHECKED BY: C. CORNWELL