



JOB: Garden State Parkway Connector over NYS Thruway (I-87)

SHEET NO: _____ OF _____

CALCULATED BY: _____ DRH Date 7/2/2026

CHECKED BY: _____ FBW Date 7/6/2026

SCALE: _____

Item: 619.10010125 INTERIM PAVEMENT MARKINGS, STRIPES (6 INCHES) TRAFFIC PAINT LF

Note: Reference Sheet No.: WZTC-09 through WZTC-20. Barrier to be moved through all WZTC stages as needed.

Description												Quantity									
	Pre-Stage I																				
	Start Station		End Station		Side		Stripes														
	118+00.00		135+00.00		RT		2.00											3400.00		LF	
	121+00.00		137+00.00		LT		3.00											4800.00		LF	
	Pre-Stage II																				
	Start Station		End Station		Side		Stripes														
	111+90.00		139+25.00		RT		2.00											5470.00		LF	
	115+75.00		140+00.00		LT		3.00											7275.00		LF	
	Stage I																				
	Start Station		End Station		Side		Stripes														
	111+60.00		138+00.00		RT		2.00											5280.00		LF	
	115+75.00		141+00.00		LT		3.00											7575.00		LF	
	Stage II																				
	Start Station		End Station		Side		Stripes														
	116+00.00		142+00.00		LT		3.00											7800.00		LF	
	Stage III																				
	Start Station		End Station		Side		Stripes														
	111+60.00		137+50.00		RT		2.00											5180.00		LF	
	116+40.00		143+00.00		LT		3.00											7980.00		LF	
	Post Stage																				
	Start Station		End Station		Side		Stripes														
	111+90.00		139+25.00		RT		2.00											5470.00		LF	
	115+75.00		140+00.00		LT		3.00											7275.00		LF	
	RFI-003: Mainline																				
	Side		Stripes																		
	EB LT		1															515.00		LF	
	WB LT		1															555.00		LF	
																</					

[illegible]



JOB: Garden State Parkway Connector over NYS Thruway (I-87)

SHEET NO: _____ OF _____

CALCULATED BY: _____ DRH Date 7/2/2026

CHECKED BY: _____ FBW Date 7/6/2026

SCALE: _____

Item: 619.1711

TEMPORARY POSITIVE BARRIER - CATEGORY 1 (PINNING PROHIBITED)

LF

Note: Reference Sheet No.: WZTC-09 through WZTC-20. Barrier to be moved through all WZTC stages as needed.

Description														Quantity						
	Stage I																			
	Start Station		End Station		Length		Side													
	124+86.60		125+42.49		55.89		LT										55.89		LF	
	128+40.47		132+00.00		359.53		LT										359.53		LF	
	118+00.00		125+42.49		742.49		RT										742.49		LF	
	128+40.47		137+00.00		859.53		RT										859.53		LF	
	Stage II																			
	Start Station		End Station		Length		Side													
	124+86.60		125+42.49		55.89		LT										55.89		LF	
	128+40.47		137+00.00		859.53		LT										859.53		LF	
	118+00.00		124+86.60		686.60		RT										686.60		LF	
	Stage III																			
	Start Station		End Station		Length		Side													
	118+00.00		125+42.49		742.49		LT										742.49		LF	
	128+40.47		137+00.00		859.53		LT										859.53		LF	
	122+25.00		125+42.49		317.49		RT										317.49		LF	
	RFI-003 Mainline																			
	Length		Side																	
	140		EB LT														140.00		LF	
	140		WB LT														140.00		LF	
									</											



JOB: Garden State Parkway Connector over NYS Thruway (I-87)

SHEET NO: _____ OF _____

CALCULATED BY: _____ FBW Date 7/2/2026

CHECKED BY: _____ FBW Date 7/6/2026

SCALE: _____

Item: 619.1716 TEMPORARY POSITIVE BARRIER - CATEGORY 6 (PINNING PERMITTED) LF

Note:

Description														Quantity						
	Pre-Stage I																			
	Start Station		End Station		Area		Side													
	121+00.00		138+50.00		1750.00		LT										1750.00		LF	
	116+30.00		135+00.00		1870.00		RT										1870.00		LF	
	Stage I																			
	Start Station		End Station		Area		Side													
	125+42.49		128+40.47		297.98		LT										297.98		LF	
	117+60.00		118+00.00		40.00		RT										40.00		LF	
	125+42.49		128+40.47		297.98		RT										297.98		LF	
	137+00.00		137+40.00		40.00		RT										40.00		LF	
	Stage II																			
	Start Station		End Station		Area		Side													
	125+42.49		128+40.47		297.98		LT										297.98		LF	
	137+00.00		137+40.00		40.00		LT										40.00		LF	
	117+60.00		118+00.00		40.00		RT										40.00		LF	
	125+42.49		128+50.00		307.51		RT										307.51		LF	
	Stage III																			
	Start Station		End Station		Area		Side													
	125+42.49		128+40.47		297.98		LT										297.98		LF	
	137+00.00		137+40.00		40.00		LT										40.00		LF	
	117+60.00		118+00.00		40.00		RT										40.00		LF	
	125+42.49		128+50.00		307.51		RT										307.51		LF	
	RFI-003 Mainline																			
	Length		Side																	
	310		EB LT														310.00		LF	
	350		WB LT														350.00		LF	
												</								



JOB: Garden State Parkway Connector over NYS Thruway (I-87)

SHEET NO: _____ OF _____

CALCULATED BY: _____ DRH _____ Date 7/2/2026

CHECKED BY: _____ FBW _____ Date 7/6/2026

SCALE: _____

Item: 619.1803 TEMPORARY IMPACT ATTENUATOR - REDIRECTIVE (TEST LEVEL 3) EACH

Note:

Description															Quantity				
RFI 003: Mainline																			
EB LT															1.00		EACH		
WB LT															1.00		EACH		