



New York State Thruway Authority

PROJECT # Statewide Pavement Safety
Striping 2027MADE BY A.P.L.DATE 6/26/26

CHECKED BY _____

DATE _____

SUBJECT New York Division.SHEET # 1OF 7Interchange 12 MP CW 10.39 :Yellow:

2,400 ft.
571 ft.
86 ft.
+ 764 ft.
3,821 ft.

White:

6" :
162 ft.
82 ft.
728 ft.
439 ft.
1,773 ft.
164 ft.
+ 1,777 ft.
5,345 ft.

Gore:

178 ft.
166 ft.
20 ft.
61 ft.
323 ft.
+ 135 ft.
883 ft.

5345 ft.
+ 883 ft.
6,228 ft.

CW 12
NE 20
NE 21

Yellow: 3,821 White: 6,228
+ 4,420 + 8,381 8,301
8,241 ft. 14,609 ft.

TOTAL: 14,529 ft.Yellow: 3,821 ft.White: 6,228 ft.

SYMBOLS:

19 - Yield Bar Triangles

Interchange 21 NE 13.91 & Interchange 20 NE 13.39 :* COMBINE *
↑
↓Yellow:

551 ft.
501 ft.
447 ft.
556 ft.
+ 2,365 ft.
4,420 ft.

White:

6" :
470 ft.
1,556 ft.
1,061 ft.
+ 3,472 ft.
6,559 ft.

Gore:

108 ft.
210 ft.
196 ft.
189 ft.
151 ft.
200 ft.
+ 195 ft.
1,249 ft.

Skip:

1,970 ft.
÷ 4
492.5 ft.
Say 493 ft.

Stop Bars:

20 ft.
x 4
80 ft.
6,559 ft.
1,249 ft.
493 ft.
+ 80 ft. *
8,381 ft. - 80 ft. = 8,301 ft.

TOTAL COMBINED:Yellow: 8,241 ft.White: 14,609 ft.TOTAL: 14,529 ft.Yellow: 4,420 ft.White: 8,381 ft.8,301 ft.Interchange 19 NE 12.48 :Yellow:

1,271 ft.
1,320 ft.
580 ft.
+ 733 ft.
3,904 ft.

White:

6" :
1,473 ft.
2,213 ft.
1,568 ft.
+ 1,774 ft.
7,528 ft.

Gore:

76 ft.
156 ft.
339 ft.
61 ft.
67 ft.
131 ft.
+ 404 ft.
1,234 ft.

7,528 ft.
+ 1,234 ft.
8,762 ft.

TOTAL:Yellow: 3,904 ft.White: 8,762 ft.



New York State Thruway Authority

PROJECT # Statewide Pavement Safety
Striping 2027.MADE BY A.P.L. DATE 6/26/26.

CHECKED BY _____ DATE _____

SUBJECT New York Division.SHEET # 2 OF 7Interchanges 18B-18A → MP NE 10.04, MP NE 10.03 & MP NE 8.86 :MP NE 10.04:Yellow:

420 ft.
612 ft.
1263 ft.
457 ft.
1,066 ft.
+ 968 ft.
4,786 ft.

White:

6" :
1,592 ft.
943 ft.
202 ft.
1,544 ft.
2,177 ft.
+ 1,041 ft.
7,499 ft.

Gore:

14 ft.
518 ft.
201 ft.
423 ft.
116 ft.
151 ft.
280 ft.
14 ft.
108 ft.
+ 116 ft.
1,941 ft.

SKIP:

380 ft.
+ 230 ft.
610 ft.
÷ 4
152.50 ft.
say 153 ft.
7,499 ft.
1,941 ft.
153 ft.
252 ft. *
+ 1262 ft.
11,107 ft. - 252 = 10,855 ft.

Stop Bars:

22 ft.
17 ft.
+ 24 ft.
63 ft.
x 4
252 ft.

Crosswalks:

All Stripes 12"
6 x 9' = 54 ft.
22 ft.
26 ft.
8 x 8' = 64 ft.
44 ft.
54 ft.
5 x 10' = 50 ft.
25 ft.
28 ft.
7 x 10' = 70 ft.
34 ft.
37 ft.
7 x 8' = 56 ft.
32 ft.
+ 35 ft.
631 ft.
(12") x 2
1,262 ft.

TOTAL:Yellow: 4,786 ft.White: 11,107 ft. 10,855 ft.M.P. NE 10.03:Yellow:

1,601 ft.
+ 620 ft.
2,221 ft.

White:

6" :
1,339 ft.
+ 2,093 ft.
3,432 ft.

Gore:

83 ft.
516 ft.
+ 252 ft.
851 ft.

3,432 ft.
+ 851 ft.
4,283 ft.

TOTAL:Yellow: 2,221 ft.White: 4,283 ft.Combined MP 10.04 & NE 10.03:

Yellow: 4,786 ft.
+ 2,221 ft.
7,007 ft.

White: 11,107 ft. 10,855 ft.
+ 4,283 ft.
15,390 ft. 15,138 ft.

TOTAL COMBINED:Yellow: 7,007 ft.

White: 15,390 ft.
15,138 ft.



New York State Thruway Authority

PROJECT # Statewide Pavement Safety
Striping 2027MADE BY A.P.C. DATE 6/26/26

CHECKED BY _____ DATE _____

SUBJECT New York DivisionSHEET # 3 OF 7Interchange 18A (MP NE 8.86):Yellow:579 ft.White:6":1,445 ft.Gore:221 ft.1,445 ft.+ 221 ft.1,666 ft.TOTAL:Yellow: 579 ft.White: 1,666 ft.Interchange 17 (MP NE 7.01):Yellow:1,493 ft.+ 2,100 ft.3,593 ft.White:6":2,713 ft.+ 2,931 ft.5,644 ft.Gore:317 ft.+ 249 ft.566 ft.STOP BARS:20 ft.X 480 ft.TOTAL:5,644 ft.566 ft.+ 80 ft.*6,290 ft.- 80 ft. = 6,210 ft.Yellow: 3,593 ft.White: 6,210 ft.Interchange 16:Yellow:1,140 ft.986 ft.595 ft.108 ft.267 ft.152 ft.84 ft.+ 281 ft.3,613 ft.White:6":1,195 ft.2,074 ft.1,744 ft.917 ft.112 ft.138 ft.58 ft.1,934 ft.+ 59 ft.8,231 ft.Gore:207 ft.213 ft.91 ft.73 ft.+ 100 ft.684 ft.SKIP:112 ft.+ 154 ft.266 ft.÷ 466.50 ft.say = 67 ft.STOP BARS:33 ft.X 4132 ft.TOTAL:Yellow: 3,613 ft.White: 9,096 ft.

LETTERS:

8 x "O"

8 x "N"

8 x "L"

8 x "Y"

SYMBOLS and ARROWS:

19 - Yield Bar Triangles

1 - Left Turn Arrow

1 - Left / Right / Straight Arrow

Interchange 16 ON RAMP TO I-95 S:Yellow:563 ft.White:6":1,798 ft.Gore:208 ft.1,798 ft.+ 208 ft.2,006 ft.TOTAL:Yellow: 563 ft.White: 2,006 ft.Yellow:3,613 ft.+ 563 ft.4,179 ft.White:~~9,096 ft.~~+ 2,006 ft.11,102 ft.8,964 ft.10,970 ft.TOTAL COMBINED INT. 16:Yellow: 4,179 ft.White: 11,102 ft.10,970 ft.



New York State Thruway Authority

PROJECT # Statewide Pavement Society
Striping 2027MADE BY A.P.L. DATE 6/26/26.

CHECKED BY _____ DATE _____

SUBJECT New York DivisionSHEET # 4 OF 7Interchange 15 MP (NE 4.63) :

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>STOP BARS:</u>
1,013 ft.	6" :	138 ft.	19 ft.
792 ft.	1,834 ft.	85 ft.	13 ft.
66 ft.	2,203 ft.	80 ft.	20 ft.
43 ft.	44 ft.	+ 140 ft.	+ 16 ft.
514 ft.	42 ft.	443 ft.	68 ft.
36 ft.	1,945 ft.		x 4
41 ft.	33 ft.		272 ft.
+ 941 ft.	90 ft.		
<u>3,446 ft.</u>	+ 1736 ft.		
	<u>7,927 ft.</u>		

TOTAL:Yellow: (3,446 ft.)White: (8,707 ft.)8,435 ft.

$$7,992 \text{ ft.} + 443 \text{ ft.} + 272 \text{ ft.} = 8,707 \text{ ft.} - 272 \text{ ft.} = 8,435 \text{ ft.}$$

~~Interchange 14 MP (NE 2.96) : * NOT IN CONTRACT - INTERCHANGE 14 MP 22.80 IS.~~

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	
747 ft.	6" :	165 ft.	3,921 ft.
+ 1,115 ft.	1,729 ft.	100 ft.	+ 534 ft.
<u>1,864 ft.</u>	+ 2,192 ft.	141 ft.	<u>4,455 ft.</u>
	<u>3,921 ft.</u>	+ 128 ft.	
		<u>534 ft.</u>	

TOTAL:Yellow: (1,864 ft.)White: (4,455 ft.)Interchange 11 MP (NE 1.11) :

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>Skip/Cat Tracks:</u>	<u>STOP BARS:</u>
330 ft.	6" :	89 ft.	102 ft.	56 ft.
181 ft.	496 ft.	259 ft.	85 ft.	x 4
+ 133 ft.	61 ft.	219 ft.	726 ft.	224 ft.
<u>644 ft.</u>	81 ft.	+ 103 ft.	+ 480 ft.	
	100 ft.	670 ft.	1,393 ft.	
	91 ft.		÷ 4	
	1017 ft.		348.25 ft.	
	+ 1,801 ft.		SAY ≈ 349 ft.	
	<u>3,647 ft.</u>			
	3,647 ft.			
	670 ft.			
	349 ft.			
	+ 224 ft. *			
	<u>4,890 ft.</u>			
	4,890 ft. - 224 ft. =			
	<u>4,666 ft.</u>			

TOTAL:Yellow: (644 ft.)White: (4,890 ft.)4,666 ft.



New York State Thruway Authority

PROJECT # Statewide Pavement Safety
Striping 2027MADE BY A.P.L. DATE 7/10/24

CHECKED BY _____ DATE _____

SUBJECT New York DivisionSHEET # 5 OF 7Interchange 11 (MP 17.63):

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>Skip/Cat Tracks:</u>	<u>Stop Bars:</u>
579 ft.	6" :	301 ft.	665 ft.	17 ft.
779 ft.	2,049 ft.	183 ft.	÷ 4	16 ft.
351 ft.	1,414 ft.	216 ft.	1666.25 ft.	+ 28 ft.
+ 184 ft.	88 ft.	+ 137 ft.	167 ft.	51 ft.
<u>1,893 ft.</u>	1,314 ft.	<u>837 ft.</u>		x 4
	+ 308 ft.			204 ft.
	<u>5,173 ft.</u>			

LETTERS: ARROWS:

1 x "O"

1 - Left Turn Arrow

1 x "N"

1 - Left / Right / Straight Arrow

1 x "L"

1 x "Y"

$$\begin{array}{r}
 5,173 \text{ ft.} \\
 837 \text{ ft.} \\
 167 \text{ ft.} \\
 + 204 \text{ ft.} \\
 \hline
 6,381 \text{ ft.} \\
 - 204 \text{ ft.} \\
 \hline
 6,177 \text{ ft.}
 \end{array}$$

TOTAL:

Yellow: 1,893 ft.White: 6,381 ft.6,177 ft.Interchange 14 (MP 22.80):

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>Skip/Cat Tracks:</u>	<u>Stop Bars:</u>	<u>Cross Walks:</u>
904 ft.	6" :	215 ft.	197 ft.	13 ft.	All Stripes 12"
Cat Tracks 103 ft.	41 ft.	213 ft.	259 ft.	64 ft.	28 x 8' = 224 ft.
÷ 4	189 ft.	246 ft.	695 ft.	39 ft.	110 ft.
26 ft.	185 ft.	537 ft.	140 ft.	14 ft.	122 ft.
863 ft.	2,924 ft.	+ 209 ft.	94 ft.	+ 50 ft.	34 x 10' = 340 ft.
419 ft.	102 ft.	1,420 ft.	122 ft.	180 ft.	+ 114 ft.
927 ft.	778 ft.		155 ft.	x 4	136 ft.
(12" DCL) 437 ft.	701 ft.		47 ft.	720 ft.	1,046 ft.
→ 437 ft.	321 ft.		41 ft.		(12") x 2
1062 ft.	157 ft.		129 ft.		
+ 1,011 ft.	1,344 ft.		397 ft.		
<u>6,086 ft.</u>	326 ft.		+ 111 ft.		
	116 ft.		2,387 ft.		
	117 ft.		÷ 4		
	117 ft.		596.75 ft.		
	+ 1,462 ft.		SAY ≈ 597 ft.		
	<u>9,029 ft.</u>				

LETTERS: ARROWS:

15 x "O"

13 - Left Turn Arrows

15 x "N"

13 - Right Turn Arrows

15 x "L"

1 - Left / Right / Straight Arrow

15 x "Y"

1 - Left / Straight Arrow

1 - Right / Straight Arrow

$$\begin{array}{r}
 9,029 \text{ ft.} \\
 1,420 \text{ ft.} \\
 597 \text{ ft.} \\
 720 \text{ ft.} \\
 + 2,092 \text{ ft.} \\
 \hline
 13,858 \text{ ft.} \\
 - 720 \text{ ft.} = 13,138 \text{ ft.}
 \end{array}$$

TOTAL:

Yellow: 6,086 ft.White: 13,858 ft.13,138 ft.



PROJECT: Installation of Pavement Markings at Various
Locations in the New York Division

MADE BY: A. Lorini

DATE: 09/2026

CHECKED BY: _____

DATE: _____

SUBJECT: White Triple Drop Stripe

SHEET # 6 OF 7

ITEM 685.1707--25 - WHITE HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)

Mainline

MP	0.00 - MP	11.30	178,992 LF
MP	29.40 - MP	38.70	147,312 LF
MP	38.70 - MP	43.00	68,112 LF
MP	43.00 - MP	45.00	31,680 LF
MP	45.00 - MP	46.00	13,200 LF
MP	68.00 - MP	72.50	59,400 LF
MP	640.00 - MP	642.40	38,016 LF

$178,992 + 147,312 + 68,112 + 31,680 + 13,200 + 59,400 + 38,016 = 536,712$

$536,712 \times 5\% = 563,560$

SAY: 563,560 LF



PROJECT: Installation of Pavement Markings at Various
Locations in the New York Division

MADE BY: A. Lorini

DATE: 09/2026

CHECKED BY: _____

DATE: _____

SUBJECT: Yellow Triple Drop Stripe

SHEET # 7 OF 7

ITEM 685.1708--25 - YELLOW HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)

Mainline

MP 0.00 - MP 11.30 119,328 LF

MP 29.40 - MP 38.70 25,344 LF

MP 38.70 - MP 43.00 98,208 LF

MP 43.00 - MP 45.00 45,408 LF

MP 45.00 - MP 46.00 21,120 LF

MP 68.00 - MP 72.50 10,560 LF

MP 640.00 - MP 642.00 47,520 LF

$$119,328 + 25,344 + 98,208 + 45,408 + 21,120 + 10,560 + 47,520 = 367,488$$

$$367,488 \times 5\% = 385,880$$

SAY: 385,880 LF