



New York State Thruway Authority

PROJECT # Statewide Pavement Safety
Striping 2027.MADE BY A.P.L. DATE 6/25/26.

CHECKED BY _____ DATE _____

SUBJECT Albany Divisions.SHEET # 1 OF 4Interchange B1:

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>Skip/Cat Tracks:</u>	<u>Stop Bars:</u>
880 ft.	6"			
1,928 ft.	4,301 ft.	157 ft.	1,619 ft.	20 ft.
Double → 2,192 ft.	3,926 ft.	189 ft.	1,628 ft.	x 4
→ 2,192 ft.	97 ft.	401 ft.	149 ft.	80 ft.
1,925 ft.	83 ft.	338 ft.	140 ft.	
737 ft.	5,726 ft.	213 ft.	644 ft.	
Double → 2,173 ft.	572 ft.	166 ft.	+ 1,014 ft.	
→ 2,173 ft.	147 ft.	225 ft.	8,441 ft. / 4 = 2,110 ft.	
902 ft.	524 ft.	204 ft.	21,498 ft.	<u>TOTAL:</u>
846 ft.	5,795 ft.	212 ft.	2,491 ft.	Yellow: <u>18,704 ft.</u>
881 ft.	+ 127 ft.	39 ft.	2,110 ft.	White: <u>26,179 ft.</u>
1,103 ft.	21,498 ft.	97 ft.	+ 80 ft. *	<u>26,099 ft.</u>
+ 172 ft.		+ 250 ft.	26,179 ft. - 80 = <u>26,099 ft.</u>	
<u>18,704 ft.</u>		<u>2,491 ft.</u>		

Interchange B2:

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>Skip/Cat Tracks:</u>	<u>TOTAL:</u>
860 ft.	6"	474 ft.	555 ft.	
4,228 ft.	3,827 ft.	183 ft.	839 ft.	Yellow: <u>9,731 ft.</u>
3,880 ft.	108 ft.	207 ft.	107 ft.	White: <u>17,053 ft.</u>
68 ft.	3,830 ft.	275 ft.	+ 719 ft.	
+ 695 ft.	3,008 ft.	90 ft.	2,220 ft. / 4 = 555 ft.	
<u>9,731 ft.</u>	+ 69 ft.	+ 311 ft.	14,622 ft.	
	+ 3,780 ft.	+ 336 ft.	1,876 ft.	
	<u>14,622 ft.</u>	<u>1,876 ft.</u>	+ 555 ft.	
			<u>17,053 ft.</u>	

Interchange 20:

<u>Yellow:</u>	<u>White:</u>	<u>Gore:</u>	<u>Skip/Cat Tracks:</u>	<u>Stop Bars:</u>
1,272 ft.	6"	389 ft.	(12") → 297 ft.	29 ft.
1,345 ft.	(12") 131 ft.	245 ft.	→ 297 ft.	+ 35 ft.
Double → 197 ft.	3,313 ft.	359 ft.	108 ft.	64 ft.
→ 197 ft.	2,725 ft.	+ 253 ft.	98 ft.	x 4
487 ft.	2,539 ft.	1,246 ft.	+ 120 ft.	256 ft.
110 ft.	67 ft.		920 ft.	
Double → 295 ft.	81 ft.		÷ 4	
→ 295 ft.	+ 191 ft.		230 ft.	
Double → 292 ft.	11,096 ft.	11,227 ft.		<u>TOTAL:</u>
→ 292 ft.	+ 131 ft.	1,246 ft.		Yellow: <u>5,281 ft.</u>
+ 499 ft.	<u>11,227 ft.</u>	230 ft.		White: <u>12,959 ft.</u>
<u>5,281 ft.</u>		+ 256 ft. *		<u>12,703 ft.</u>
		<u>12,959 ft. - 256 = 12,703 ft.</u>		

SYMBOLS:

Letters:

4 x "O", 4 x "N", 4 x "L", 4 x "Y"

Arrows:

3 - Left/Straight? Right Arrows

1 - Left/Straight

5 - Yield Bar Triangles



New York State Thruway Authority

PROJECT # Statewide Pavement Safety
Striping 2027MADE BY A.P.L. DATE 6/25/26.

CHECKED BY _____ DATE _____

SUBJECT Albany Divisions.SHEET # 2 OF 4Interchange 25:****REMOVED - Was part of Contract TAA 25-24****Yellow:

$$\begin{array}{r}
 4,280 \text{ ft.} \\
 3,889 \text{ ft.} \\
 636 \text{ ft.} \\
 843 \text{ ft.} \\
 + 1,124 \text{ ft.} \\
 \hline
 10,772 \text{ ft.}
 \end{array}$$
White:

$$\begin{array}{r}
 6'' \\
 3,890 \text{ ft.} \\
 3,489 \text{ ft.} \\
 4,320 \text{ ft.} \\
 470 \text{ ft.} \\
 + 4,753 \text{ ft.} \\
 \hline
 16,922 \text{ ft.}
 \end{array}$$
Gore:

$$\begin{array}{r}
 232 \text{ ft.} \\
 125 \text{ ft.} \\
 355 \text{ ft.} \\
 299 \text{ ft.} \\
 253 \text{ ft.} \\
 434 \text{ ft.} \\
 256 \text{ ft.} \\
 + 180 \text{ ft.} \\
 \hline
 2,134 \text{ ft.}
 \end{array}$$
Skip/Cat Tracks:

$$\begin{array}{r}
 5,125 \text{ ft.} \\
 (12'') \rightarrow 994 \text{ ft.} \\
 \rightarrow 994 \text{ ft.} \\
 3,226 \text{ ft.} \\
 483 \text{ ft.} \\
 + 1,336 \text{ ft.} \\
 \hline
 12,158 \text{ ft.}
 \end{array}$$
TOTAL:

$$\begin{array}{r}
 12,158 \text{ ft.} \\
 \div 4 \\
 \hline
 3,039.50 \text{ ft.} \\
 = 3,040 \text{ ft.}
 \end{array}$$
Yellow: 10,772 ft.White: 22,096 ft.Interchange 29:Yellow:

$$\begin{array}{r}
 \text{(Cat Tracks)} 200 \text{ ft.} \\
 \div 4 \\
 \hline
 50 \text{ ft.} \\
 2,601 \text{ ft.} \\
 2,417 \text{ ft.} \\
 \text{Double} \rightarrow 459 \text{ ft.} \\
 \rightarrow 459 \text{ ft.} \\
 766 \text{ ft.} \\
 + 882 \text{ ft.} \\
 \hline
 7,634 \text{ ft.}
 \end{array}$$
White:

$$\begin{array}{r}
 6'' \\
 3,007 \text{ ft.} \\
 3,117 \text{ ft.} \\
 448 \text{ ft.} \\
 486 \text{ ft.} \\
 147 \text{ ft.} \\
 + 3,031 \text{ ft.} \\
 + 2,570 \text{ ft.} \\
 \hline
 12,806 \text{ ft.}
 \end{array}$$
12'':

$$\begin{array}{r}
 366 \text{ ft.} \\
 241 \text{ ft.} \\
 97 \text{ ft.} \\
 + 20 \text{ ft.} \\
 \hline
 724 \text{ ft.} \\
 \times 2 \\
 \hline
 1,448 \text{ ft.}
 \end{array}$$
Gore:

$$\begin{array}{r}
 134 \text{ ft.} \\
 259 \text{ ft.} \\
 412 \text{ ft.} \\
 363 \text{ ft.} \\
 343 \text{ ft.} \\
 + 347 \text{ ft.} \\
 \hline
 1,858 \text{ ft.}
 \end{array}$$
Skip/Cat Tracks:

$$\begin{array}{r}
 101 \text{ ft.} \\
 90 \text{ ft.} \\
 233 \text{ ft.} \\
 + 281 \text{ ft.} \\
 \hline
 705 \text{ ft.} \\
 \div 4 \\
 \hline
 176.25 \text{ ft.} \\
 \text{Say } 176 \text{ ft.}
 \end{array}$$
Stop Bars:

$$\begin{array}{r}
 20 \text{ ft.} \\
 \times 4 \\
 \hline
 80 \text{ ft.}
 \end{array}$$
Crosswalks:

$$\begin{array}{r}
 23 \times 13' \\
 = 299 \text{ ft.} \\
 62 \text{ ft.} \\
 + 29 \text{ ft.} \\
 \hline
 390 \text{ ft.} \\
 (12'') \times 2 \\
 \hline
 780 \text{ ft.}
 \end{array}$$

$$\begin{array}{r}
 12,806 \text{ ft.} \\
 1,448 \text{ ft.} \\
 1,858 \text{ ft.} \\
 176 \text{ ft.} \\
 80 \text{ ft.} * \\
 + 780 \text{ ft.} \\
 \hline
 17,148 \text{ ft.}
 \end{array}$$

$$17,148 \text{ ft.} - 80 = 16,068 \text{ ft.}$$
TOTAL:Yellow: 7,634 ft.White: 17,148 ft.16,068 ft.



PROJECT: Installation of Pavement Markings at Various
Locations in the Albany Division

MADE BY: A. Lorini

DATE: 09/2026

CHECKED BY: _____

DATE: _____

SUBJECT: White Triple Drop Stripe

SHEET # 3 OF 4

ITEM 685.1707--25 - WHITE HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)

Mainline

MP 161.30 - 163.30 26,400 LF

MP 170.00 - MP 180.00 132,000 LF

MP 180.00 - MP 190.00 132,000 LF

26,400 + 132,000 + 132,000 = 290,400

290,400 x 5% = 304,920

SAY: 304,920 LF



PROJECT: Installation of Pavement Markings at Various
Locations in the Albany Division

MADE BY: A. Lorini

DATE: 09/2026

CHECKED BY: _____

DATE: _____

SUBJECT: Yellow Triple Drop Stripe

SHEET # 4 OF 4

ITEM 685.1708--25 - YELLOW HIGHLY REFLECTORIZED TRIPLE DROP EPOXY PAVEMENT STRIPE (LF)

Mainline

MP 161.30 - 163.30 MP 21,120 LF

170.00 - MP 180.00 MP 132,000 LF

180.00 - MP 190.00 MP 132,000 LF

21,120 + 132,000 + 132,000 = 232,320

232,320 x 5% = 243,940

SAY: 243,940 LF